GENERAL COMMENT:

All electrical shown on this drawing not highlighted is to remain without modification

DRYER ROOM
M306
PRESS BUILDING
M305
CONTROL BUILDING
BLOWER ROOM
HH-9 EXISTING HANDHOLE
HH-10 NEW HANDHOLE
HH-11 EXISTING HANDHOLE
HH-12
HH-13
HH-14
HH-6
HH-7
HH-8
HH-4
HH-5
HH-3
HH-1
HH-2
EXISTING UNDERGROUND POWER AND TELEPHONE SERVICES
SEE DRAWING E11 FOR FURTHER ROUTING
TREATMENT UNIT
GROUND RODS
INFLUENT P.S.
HEADWORKS AREA
CHLORINE GENERATION BUILDING
CONDUITS TO STORAGE TANK SEE CIVIL DRAWINGS FOR FURTHER ROUTING
A E18

DRAWING NOTES:

1. ASSUMED UNDERGROUND ROUTING OF ORIGINAL CONDUIT SHOWN. CONTRACTOR TO USE LOCATING AGENCY TO DETERMINE ACTUAL ROUTING BEFORE PROCEEDING WITH EARTHWORK.
2. CONTRACTOR SHALL COORDINATE ROUTING OF ELECTRICAL CONDUITS WITH NEW PIPING SHOWN ON CIVIL DRAWINGS TO ENSURE THAT ELECTRICAL IS NOT ROUTED IN PARALLEL ABOVE PIPING AND THAT WHEN ROUTED ADJACENT IS KEPT AT 12 INCH MINIMUM SEPARATION.

OVERALL SITE POWER AND SIGNAL PLAN

SCALE: 1" = 10' 0 1 2 3 4 5 10

Change Order No. 1 Coordination Richard Sample, P.E. July 12, 2019

RSE RICHARD SAMPLE ENGINEERING
1197 Magnolia Ave, Redding, CA 96001
530-242-1134 Fax: 530-242-1136
E-mail: rse@integrity.com

REGISTERED PROFESSIONAL ENGINEER RICHARD A SAMPLE 16423 EXP. 06/30/19 ELECTRICAL STATE OF CALIFORNIA

VERIFY SCALES
BAR IS ONE INCH ON ORIGINAL DRAWING 0 1"
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

SHN CONSULTING ENGINEERS & GEOLOGISTS, INC.
335 S. MAIN ST. WILLITS, CA. 95490
WWW.SHN-ENGR.COM 707-459-4518

DSGN	RS
DR	MAS
CHK	
APVD	

NO.	REVISION	BY	DATE

MENDOCINO CITY CSD
PLANT IMPROVEMENTD AND RECYCLED WATER SYSTEM
MENDOCINO, CALIFORNIA

OVERALL SITE POWER AND SIGNAL PLAN

SHEET E3
SEQ –
DATE 4/2019
PROJ. NO. 517002